1. | FULL HEIGHT STORAGE CABINETS (UNO) SHALL BE 2'-0" DEEP. 2'-0" MAXIMUM DOOR WIDTH. WARDROBE CABINETS TO 7 PROVIDE (5) ADJ PLAM ى WHERE INDICATED. PROVIDE CONTINUOL JACKSPLASH/SIDESPLASHES. JABINETS ARE OVER 3'-0" WIDE. PROVIDE 1" THICK SHELV PROVIDE GROMMETS AT WORKSTATIONS, INCLUDING NURSE STATIONS. RECEPTION DESKS AND OTHER WORK COUNTERS. CUT IN FIELD-PROVIDE ONE PER ELECTRICAL DEVICE BELOW COUNTER-COORDINATE LOCATIONS WITH OWNER. COLOR TO BE SELECTED BY ARCHITECT. SEE SPECIFICATION FOR GROMMET TYPES AND SIZES. PROVIDE A 2" RADIUSED EDGE (IN PLAN) AT ALL OUTSIDE, EXPOSED COUNTERTOP CORNERS (UNO). ALL PLAM COUNTERTOPS SHALL HAVE A 1 1/4" THICK PLAM SQUARE EDGE NOSING (UNO).

ALL COUNTERTOPS ARE 2'-1" DEEP (UNO).

PROVIDE PLYWOOD BACKUP AT ALL SSM COUNTERTOPS.

- 11. COUNTERTOP SUPPORT BRACKETS ARE PROVIDED BY THE CASEWORK SUPPLIER. PROVIDE WALL BLOCKING AT EACH SUPPORT.
- 12. COORDINATE LOCATION OF ALL UNDERCOUNTER SUPPORT WITH OWNER FURNISHED/OWNER INSTALLED EQUIPMENT.
- 13. NO EXPOSED FASTENERS ON CASEWORK (UNO).
- 14. | ALL EXPOSED METAL CLIP ANGLES AND BRACKETS TO BE PAINTED TO MATCH | CASEWORK.
- 15. ALL EXPOSED AND SEMI-EXPOSED SURFACES OF CASEWORK, SHELVING, BASE, FULL HEIGHT AND UPPER WALL CABINETS, AND FINISHED END PANELS ARE PLAM (UNO).
- 16. | FIELD VERIFY SPACE AVAILABLE AT CABINET LOCATIONS PRIOR TO CASEWORK FABRICATION.
- 17. RETURN BACKSPLASH AT SIDEWALLS (UNO).
- 18. TUCK WALL COVERING BEHIND ALL BACKSPLASHES.
- 19. ALL CABINETS TO RECEIVE BASE SCHEDULED FOR ROOM (UNO).
- 20. COORDINATE ALL SWITCHES, UNDER-CABINET LIGHT FIXTURES AND UNDERCOUNTER RECEPTACLES WITH THE ELECTRICAL CONTRACTOR.
- 21. PROVIDE HANGING FILE EDGE/HARDWARE WHERE FILE DRAWERS ARE INDICATED.
- 22. PROVIDE A 1/4" GAP BETWEEN BOTTOM EDGE OF COUNTERTOP AND TOP EDGE OF DOOR FRONTS/DOORS OF CABINETS.
- 23. REFER TO FINISH PLAN GENERAL NOTES FOR CASEWORK FINISHES (UNO).
- 24. BASE AS SCHEDULED (UNO).
- 25. PLAM COUNTERTOPS TO RECEIVE 3mm FLAT PVC EDGE (UNO).